## LAN setup at Noakhali and Jhalakathi Office: BOQ

SI#	Item name	Unit	Noakhali	Jhalakathi	Total	Unit	Total	Remarks
					Qty.	Price	Price	
1	RJ45 cat6 modular	Pcs	50	50	100			
2	Single MK box	Pcs	15	15	30			
3	Double MK box	Pcs	5	5	10			
4	Single type faceplate	Pcs	25	25	50			
5	Patch panel (24port)	Pcs	1	1	2			
6	Cable manager with cover	Set	2	2	4			
7	9u wall mount data cabinet	Pcs	1	1	2			
8	1/2 meter cat6 patch cord	Pcs	25	25	50			
9	Cat6 UTP Solid Cable 23AWG	box	2	0	2			
	305m/box							
	Installation-Hardware &	Job	1	1	2			
10	Accessories (as per attached							
	Annexure 02)							

Annexure-02

## Jhalakathi Office:

Will complete bellow tasks:

- 1. 1pcs 9u wall mount data cabinet fix in wall
- 2. 1pcs 24 port patch panel fix in cabinet
- 3. 1pcs 24 port cable manager fix in cabinet
- 4. 48pcs RJ-45 modular punch(24 for patch panel+24 for user end)
- 5. 20 pcs single MK box with faceplate fix in wall
- 6. LAN cable installed for 5 user point

## **Noakhali Office:**

Will complete bellow tasks:

- 1. 1pcs 9u wall mount data cabinet fix in wall
- 2. 1pcs 24 port patch panel fix in cabinet
- 3. 1pcs 24 port cable manager fix in cabinet
- 4. 48pcs RJ-45 modular punch(24 for patch panel+24 for user end)
- 5. 20 pcs single MK box with faceplate fix in wall
- 6. LAN cable installed for 20 user point